10/582427

IAP20 Rec'd PCT/PTO 08 JUN 2006

中华人民共和国国家知识产权局 STATE INTELLECTUAL PROPERTY OFFICE OF THE PEOPLE'S REPUBLIC OF CHINA



证明

CERTIFICATE

本证明之附件是向中国专利局作为受理局提交的下列国际申请副本
THIS IS TO CERTIFY THAT ANNEXED HERETO IS A TRUE COPY OF THE BELOW
IDENTIFIED INTERNATIONAL APPLICATION THAT WAS FILED WITH THE
CHINESE PATENT OFFICE AS RECEIVING OFFICE

国际申请号:

PCT/CN2005/001960

INTERNATIONAL APPLICATION NUMBER

国际申请日:

18.11月 2005(18.11.2005)

INTERNATILNAL FILING DATE

发明名称:

LATENCY HIDING OF TRACES USING BLOCK COLORING

TITLE OF INVENTION

中华人民共和国国家知识产权局局长
COMMISSIONER OF THE STATE INTELLECTUAL PROPERTY
OFFECE OF THE PEOPLE'S REPUBLIC OF CHINA

CERTIFIED COPY OF PRIORITY DOCUMENT

田力黄

二零零六年四月十日 APRIL 10, 2006



COPY

PCT

REQUEST

The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty.

For receiving Office use only
PCT/CN 2005 / 0 0 1 9 6 0
18·11月2005 (18·11·2005)
RO/CN 中华人民共和国国家知识产权局 PCT International Application

Applicant's or agent's file reference (if desired) (12 characters maximum) FPEL05150059

	(ij aestrea) (12 characte	ers maximum) FF	7ELU3 130039	
Box No. I TITLE OF INVENTION LATENCY HIDING OF TRACES USING BLOC	K COLORING	-		
Box No. II APPLICANT This person	n is also inventor			
Name and address: (Family name followed by given name; for a legal en The address must include postal code and name of country. The country of Box is the applicant's State (that is, country) of residence if no State of residen	the address indicated in this	Telephone No.		
INTEL CORPORATION 2200 Mission College Blvd.	,	Facsimile No.		
Santa Clara, California 95052 United States of America		Teleprinter No.		
		Applicant's regis	stration No. with the Office	
State (that is, country) of nationality: US	State (that is, country) US	of residence:		
This person is applicant for the purposes of: all designated States all designated the United States		the United States of America only	the States indicated in the Supplemental Box	
Box No. III FURTHER APPLICANT(S) AND/OR (FURT	HER) INVENTOR(S)			
Name and address: (Family name followed by given name; for a legal ent The address must include postal code and name of country. The country of Box is the applicant's State (that is, country) of residence if no State of residence GUO, Xiaofeng Room 301, Building 13, No. 451, Xianxia Road Shanghai 21000 P. R. of China	the address indicated in this	inventor marked,	nt only nt and inventor r only (If this check-box is do not fill in below.) stration No. with the Office	
State (that is, country) of nationality: CN	State (that is, country) CN	of residence:		
This person is applicant for the purposes of: all designated all designated the United S		the United States of America only	the States indicated in the Supplemental Box	
Further applicants and/or (further) inventors are indicated of	on a continuation sheet.			
Box No. IV AGENT OR COMMON REPRESENTATIVE	; OR ADDRESS FOR	CORRESPOND	ENCE	
The person identified below is hereby/has been appointed to act of the applicant(s) before the competent International Authorities		agent	common representative	
Name and address: (Family name followed by given name; for a legal ent. The address must include postal code and name of c	ity, full official designation. country.)	Telephone No. (852)28284	4688	
China Patent Agent (H.K.) Ltd. 22/F, Great Eagle Centre	-	Facsimile No. (852)28271	-	
23 Harbour Road, Wanchai Hong Kong Special Administrative Region		Teleprinter No.		
The People's Republic of China		Agent's registrati	ion No. with the Office	
Address for correspondence: Mark this check-box where space above is used instead to indicate a special address to	no agent or common rep which correspondence sh	resentative is/has l rould be sent.	been appointed and the	

0 2 · 2 F 2003 (0 2 · 0 2 9 6 6 6 6 PCT/CN 2005 7 0 0 1 9 6 6 6 6

Sheet No2						
Continuation of Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)						
If none of the following sub-boxes is used, this sheet should not be included in the request.						
Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.) DAI, Jinquan Room 309, Block 2, Ren Le Xin Cun, Songjiang District Shanghai 210000 P. R. of China	This person is: applicant only applicant and inventor inventor only (If this check-box is marked, do not fill in below.) Applicant's registration No. with the Office					
State (that is, country) of nationality: CN State (that is, country) CN) of residence:					
This person is applicant all designated all designated States except the United States of America	the United States of America only the States indicated in the Supplemental Box					
Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.) LI, Long Room 202, Building 34, No. 123, Fuguan Road Shanghai 210000 P. R. of China	This person is: applicant only applicant and inventor inventor only (If this check-box is marked, do not fill in below.) Applicant's registration No. with the Office					
State (that is, country) of nationality: CN State (that is, country) CN) of residence:					
This person is applicant for the purposes of: all designated all designated States except the United States of America	the United States of America only the States indicated in the Supplemental Box					
Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.) LV, Zhiyuan Room 202, Building 8, Yongila St., Luwan District Shanghai 21000 P. R. of China	This person is: applicant only applicant and inventor inventor only (If this check-box is marked, do not fill in below.) Applicant's registration No. with the Office					
State (that is, country) of nationality: CN State (that is, country) CN) of residence:					
This person is applicant for the purposes of: all designated all designated States except the United States of America	the United States of America only the States indicated in the Supplemental Box					
Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)	This person is: applicant only applicant and inventor inventor only (If this check-box is marked, do not fill in below.) Applicant's registration No. with the Office					
State (that is, country) of nationality: State (that is, country)	of residence:					
This person is applicant all designated all designated States except for the purposes of:	the United States of America only the States indicated in the Supplemental Box					
Further applicants and/or (further) inventors are indicated on another continuation sheet.						

Form PCT/RO/101 (continuation sheet) (January 2004)

See Notes to the request form

Sheet No. ...?.. Continuation of Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S) If none of the following sub-boxes is used, this sheet should not be included in the request. Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.) This person is: applicant only DAI, Jason applicant and inventor Room 309, Block 2, inventor only (If this check-box Ren Le Xin Cun, Songjiang District is marked, do not fill in below.) Shanghai 210000 P. R. of China Applicant's registration No. with the Office State (that is, country) of nationality: State (that is, country) of residence: CN the States indicated in the Supplemental Box This person is applicant all designated States all designated States except the United States of America the United States of America only for the purposes of: Name and address: (Family name followed by given name; for a legal entity. full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.) This person is: applicant only LI, Long applicant and inventor Room 202, Building 34, inventor only (If this check-box No. 123, Fuguan Road is marked, do not fill in below.) Shanghai 210000 P. R. of China Applicant's registration No. with the Office State (that is, country) of nationality: State (that is, country) of residence: CN CN all designated This person is applicant all designated States except the United States of America the United States of America only the States indicated in the Supplemental Box for the purposes of: Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.) This person is: applicant only LU, Zhiyuan applicant and inventor Room 202, Building 8, inventor only (If this check-box Yongila St., Luwan District is marked, do not fill in below.) Shanghai 21000 Applicant's registration No. with the Office P. R. of China State (that is, country) of nationality: State (that is, country) of residence: CN CN all designated States except the United States of America This person is applicant all designated the United States the States indicated in the Supplemental Box for the purposes of: of America only Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this This person is: Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.) applicant only applicant and inventor inventor only (If this check-box is marked, do not fill in below.) Applicant's registration No. with the Office

State (that is, country) of residence:

the United States

of America only

all designated States except the United States of America

Form PCT/RO/101 (continuation sheet) (January 2004)

all designated

Further applicants and/or (further) inventors are indicated on another continuation sheet.

State (that is, country) of nationality:

This person is applicant

for the purposes of:

the States indicated in

the Supplemental Box

IPTI MITTING	•	15	v	J.	_	U Y
. •						11.
						- 41
						* The state of
						San Contract

		Sheet No3		*		
Box No. V DESIGNAT	HONS					
The filing of this request con filing date, for the grant of e	nstitutes under Rule 4.9(a), the every kind of protection availal	he designation of all Cont able and, where applicable	racting States bound by the country for the grant of both reg	he PCT on the international gional and national patents.		
However,						
DE Germany is not de	esignated for any kind of natio	onal protection				
KR Republic of Korea	a is not designated for any kir	nd of national protection				
RU Russian Federatio	on is not designated for any ki	ind of national protection				
the national law, of an earlie	v be used to exclude (irrevocabl er national application from w s in these and certain other St	which priority is claimed. S				
Box No. VI PRIORITY	CLAIM					
The priority of the following	g earlier application(s) is hereb	by claimed:				
Filing date	Number	7	Where earlier application	is:		
of earlier application (day/month/year)	of earlier application	national application: country or Member of WTO	regional application:* regional Office	international application: receiving Office		
item (1)	,					
item (2)						
			1	<u> </u>		
item (3)						
Further priority claims a	are indicated in the Supplemen	ntal Box.				
The receiving Office is reque the earlier application was fil above as:	ested to prepare and transmit to led with the Office which for th	o the International Bureau he purposes of this interna	a certified copy of the eartional application is the r	rlier application(s) (only if eceiving Office) identified		
	em (1) item (2)) item (3)) other, se	ee Supplemental Box		
Industrial Property or one Me	on is an ARIPO application, in Tember of the World Trade Org	yanization for which that e	earlier application was file	led (Rule 4.10(b)(ii)):		
	TIONAL SEARCHING AUT					
Choice of International Sea international search, indicate ISA / CN	arching Authority (ISA) (if two the Authority chosen; the two-		Searching Authorities are	competent to carry out the		
	urlier search reference to th	• '	· · · · · · · · · · · · · · · · · · ·			
International Searching Author	rlier search; reference to th ority):	iat search (i) an earner se	earch has been carried out	t by or requestea from the		
Date (day/month/year)	Numbe	er Coun	ntry (or regional Office)			
Box No. VIII DECLARAT						
	are contained in Boxes Nos. Vate in the right column the number			Number of declarations		
Box No. VIII (i)	Declaration as to the identity	y of the inventor		:		
Box No. VIII (ii)	Declaration as to the application date, to apply for and be gra		e international filing	:		
Box No. VIII (iii)	Declaration as to the applic date, to claim the priority o		he international filing	:		
Box No. VIII (iv) Declaration of inventorship (only for the purposes of the designation of the United States of America):						
Box No. VIII (v)	Declaration as to non-prejuc	dicial disclosures or exce	ptions to lack of novelty	:		

		4
Sheet	No	4

This international application contains:		ernational application is accompanied by the followin				
(a) in paper form, the following number of		item(s) (mark the applicable check-boxes below and indicate in of item right column the number of each item):				
sheets:		fee calculation sheet	. 4			
request (including declaration sheets) : 4		original separate power of attorney	. 1			
description (excluding			; 1			
sequence listing and/or		original general power of attorney	;			
tables related thereto) : 18	4. 🗀	copy of general power of attorney; reference number if any:	•			
claims : 6	٦, ٦	statement explaining lack of signature				
abstract : 1			:			
drawings : 11	l ₀. ⊔	priority document(s) identified in Box No. VI as item(s):				
Sub-total number of sheets : 40	7. 🗖	translation of international application into	•			
sequence listing :		(language):	:			
tables related thereto : (for both, actual number of	8. 🗆	separate indications concerning deposited microorgan or other biological material	nism :			
sheets if filed in paper form, whether or not also filed in	9. 🗆	sequence listing in computer readable form (indicate type and number of carriers)				
computer readable form; see (c) below) ————————————————————————————————————	(i)	copy submitted for the purposes of international se Rule 13ter only (and not as part of the international	arch under			
Total number of sheets : 40	(ii)	(only where check-box (b)(i) or (c)(i) is marked in left additional copies including, where applicable, the				
(b) only in computer readable form (Section 801(a)(i))		purposes of international search under Rule 13ter	:			
(i) ☐ sequence listing (ii) ☐ tables related thereto		together with relevant statement as to the identity of copies with the sequence listing mentioned in left of	column :			
(c) also in computer readable form (Section 801(a)(ii))	10.	tables in computer readable form related to sequence l (indicate type and number of carriers)	isting			
(i) sequence listing (ii) tables related thereto	(i)	copy submitted for the purposes of international se Section 802(b-quater) only (and not as part of the				
Type and number of carriers (diskette,	(;;)	application) (only where check-box (b)(ii) or (c)(ii) is marked in le	: :			
CD-ROM, CD-R or other) on which are contained the	(11)	additional copies including, where applicable, the	copy for the			
sequence listing:						
tables related thereto:						
items 9(ii) and/or 10(ii), in right column)		outs (specify)				
Figure of the drawings which should accompany the abstract:	internati	ge of filing of the onal application:				
Box No. X SIGNATURE OF APPLICANT Next to each signature, indicate the name of the person sign	T, AGEN	GENALONESPRESENTATIVE	from reading the request)			
The court of the court of the persons se	ang una me	(10) 16	from reading the requesty.			
	1	(至年界利中特别区)				
	1	四年月章 小厂				
		* 63				
	F	eceiving Office use only				
1. Date of actual receipt of the purported		eceiving Office use only	2 D			
international application: 18	· 11H	2005 (1 3 · 1 1 · 2 0 0 5)	2. Drawings:			
2 Corrected data of compileration during the 1			received:			
 Corrected date of actual receipt due to later b timely received papers or drawings completing the purported international application: 	ut Ig					
4. Date of timely receipt of the required			not received:			
corrections under PCT Article 11(2):						
5. International Searching Authority (if two or more are competent): ISA / 6. Transmittal of search copy delayed until search fee is paid						
	r or mie	national Bureau use only				
Date of receipt of the record copy						
by the International Bureau:						



This sheet is not part of and does not count as a sheet of the international application.

PCT

FEE CALCULATION SHEET Annex to the Request

PCT/CN 2005 / 0 0 1 9 6 0
International Application No.

Applicar file refer	nt's or agent's ence	PEL05150059	Date stamp	115 2005 of the receiving	(1 g , 1	1 · 2005
Applicar	L CORPORATION	etc				
			•			
	ILATION OF PRESCRIBEI INSMITTAL FEE) rees	L	CNY500	T	CNYSUO
1. 1101				CNY1500) [5]	COLVIDO
	RCH FEE	CNI	L	<u> </u>)	- C/4 / (500 -
(If tv	vo or more International Seas	rching Authorities are competent				
	national search, indicate the international search.)	name of the Authority which is c	nosen to car	ry out		
3. INT	ERNATIONAL FILING FEE					
		No. IX apply, enter Sub-total nui . IX do not apply, enter Total nui			-	
il	first 30 sheets		CHF140	0 [i1]		CAFIGO
ि	10	x CHF15 =	CHF150	i2		CHEISO
[12]	number of sheets in excess of 30	fee per sheet	<u></u>			
<u></u>			<u>.</u>			
_	thereto are filed in computer	f sequence listing and/or tables re readable form under Section 801 aper, under Section 801(a)(ii)):				
•	400	x =		i3		
		fee per sheet	I CHF1	1550 [_	CHF1550
Add	amounts entered at i1, i2 and	i3 and enter total at I	<u> Cirii i</u>	1 330	<u> </u>	<u>(x1F1030</u>
interi	national filing fee. Where th	re entitled to a reduction of 75 ne applicant is (or all applicants l is 25% of the international filin	s are) so			
			1		P	
4. FEE	FOR PRIORITY DOCUMEN	IT (if applicable)	; L			CNYLOW
£ TOT	AL FEES PAYABLE			CNY2000	OCHF1539	CHYLONO _
		P, and enter total in the TOTAL b	ox [TOTA	L.	-
	······					
_	OF PAYMENT norization to charge		7 anst	r		
dep	osit account (see below)	postal money order	cash		coupons	
che		bank draft	revenue s	stamps L	other (speci	(y):
	RIZATION TO CHARGE (de of payment may not be avail	OR CREDIT) DEPOSIT ACCO	JUNI	Receiving Office	CENT ON	
Г ⊊71 ∧	thorization to charge the total	fees indicated above		Deposit Accord	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
_	thorization to charge the total : is check-box may be marked on	ly if the conditions for deposit accou	ints	Date:	到4月10日	5 0
of ti	he receiving Office so permit) A credit any overpayment in the	uthorization to charge any deficies	ncy	Name:	2 8 W	
X Au	thorization to charge the fee fo	or priority document.		Signature:	*	63//



PCT/CN 2005 / 0 0 1 9 6 0

LATENCY HIDING OF TRACES USING BLOCK COLORING BACKGROUND

FIELD OF THE INVENTION

[001] Embodiments of the invention relate to the field of software, and more specifically, to program transformation.

DESCRIPTION OF RELATED ART.

[002] Modern network processors generally have asynchronous, or non-blocking, memory access operations, so that other computation work may be overlapped with the latency of the memory accesses. For instance, every memory access instruction is nonblocking and is associated with an event signal. That is, when a memory access instruction is issued, other instructions following it may continue to run while the memory access is in flight, until a wait instruction for the associated signal blocks the execution. Once the memory access is completed (e.g., its result is available), the associated signal is asserted by the hardware and the wait instruction then clears the signal and returns to execution. Consequently, all the instructions between the memory access instruction and the wait instruction may be overlapped with the latency of the memory access. In addition, modern network processors usually have a highly parallel architecture and are multi-threaded. For example, whenever a new packet arrives, a series of tasks (e.g., receipt of the packet, routing table look-up, and en-queuing) is performed on that packet by a new thread. In such a parallel programming paradigm, accesses to global resources (e.g., memory) are protected by critical sections to ensure the mutual exclusiveness and synchronizations between threads

[003] Together with the asynchronous memory access operations, the multithreading/multi-processing programming model helps hide the long memory access latency, by overlapping the latency of the memory access in one thread with the latency of memory accesses and/or the computations in other threads. However, if both the memory access and its associated wait instruction are contained in the same critical section, the memory latency hiding is greatly impacted due to the sequential execution of the critical section between threads. This may result in performance degradation.





BRIEF DESCRIPTION OF THE DRAWINGS

[004] Embodiments of invention may best be understood by referring to the following description and accompanying drawings that are used to illustrate embodiments of the invention. In the drawings:

[005] Figure 1A is a diagram illustrating a system in which one embodiment of the invention can be practiced.

[006] Figure 1B is a diagram illustrating a host processor system according to one embodiment of the invention.

[007] Figure 2A is a diagram illustrating a program module of program traces with a critical section according to one embodiment of the invention.

[008] Figure 2B is a diagram illustrating coloring blocks in the program traces according to one embodiment of the invention.

[009] Figure 3A is a diagram illustrating speculative moving of wait instruction according to one embodiment of the invention.

[0010] Figure 3B is a diagram illustrating intermediate moving of wait instruction according to one embodiment of the invention.

[0011] Figure 3C is a diagram illustrating final moving of wait instruction according to one embodiment of the invention.

[0012] Figure 4 is a diagram illustrating update of color information when sinking critical section begin according to one embodiment of the invention.

[0013] Figure 5 is a flowchart illustrating a process to hide latency of a program trace according to one embodiment of the invention.

[0014] Figure 6 is a flowchart illustrating a process to associate blocks with color information according to one embodiment of the invention.





[0015] Figure 7 is a flowchart illustrating a process to sink the wait instruction according to one embodiment of the invention.

[0016] Figure 8 is a flowchart illustrating a process to update the color information according to one embodiment of the invention.

[0017] Figure 9 is a diagram illustrating a compiler to enhance latency hiding according to one embodiment of the invention.





DESCRIPTION

[0018] An embodiment of the present invention is a technique to hide latency in program traces. Blocks of instructions between start and end of a critical section are associated with color information. The blocks correspond to a program trace and containing a wait instruction. The wait instruction is sunk down the blocks globally to the end of the critical section using the color information and a dependence constraint on the wait instruction.

[0019] In the following description, numerous specific details are set forth. However, it is understood that embodiments of the invention may be practiced without these specific details. In other instances, well-known circuits, structures, and techniques have not been shown to avoid obscuring the understanding of this description.

[0020] One embodiment of the invention may be described as a process which is usually depicted as a flowchart, a flow diagram, a structure diagram, or a block diagram. Although a flowchart may describe the operations as a sequential process, many of the operations can be performed in parallel or concurrently. In addition, the order of the operations may be re-arranged. A process is terminated when its operations are completed. A process may correspond to a method, a program, a procedure, a method of manufacturing or fabrication, etc.

[0021] Elements of embodiments of the invention may be implemented by hardware, firmware, software or any combination thereof. The term hardware generally refers to an element having a physical structure such as electronic, electromagnetic, optical, electro-optical, mechanical, electro-mechanical parts, components, or devices, etc. The term software generally refers to a logical structure, a method, a procedure, a program, a routine, a process, an algorithm, a formula, a function, an expression, etc. The term firmware generally refers to a logical structure, a method, a procedure, a program, a routine, a process, an algorithm, a formula, a function, an expression, etc., that is implemented or embodied in a hardware structure (e.g., flash memory). Examples of firmware may include microcode, writable control store, micro-programmed structure. When implemented in software or firmware, the elements of an embodiment of the present invention are essentially the code segments to perform the necessary tasks. The



software/firmware may include the actual code to carry out the operations described in one embodiment of the invention, or code that emulates or simulates the operations. The program or code segments can be stored in a processor or machine accessible medium or transmitted by a computer data signal embodied in a carrier wave, or a signal modulated by a carrier, over a transmission medium. The "processor readable or accessible medium" or "machine readable or accessible medium" may include any medium that can store, transmit, or transfer information. Examples of the processor readable or machine accessible medium include an electronic circuit, a semiconductor memory device, a read only memory (ROM), a flash memory, an erasable ROM (EROM), an erasable programmable ROM (EPROM), a floppy diskette, a compact disk (CD) ROM, an optical disk, a hard disk, a fiber optic medium, a radio frequency (RF) link, etc. The computer data signal may include any signal that can propagate over a transmission medium such as electronic network channels, optical fibers, air, electromagnetic, RF links, etc. The code segments may be downloaded via computer networks such as the Internet, Intranet, etc. The machine accessible medium may be embodied in an article of manufacture. The machine accessible medium may include data that, when accessed by a machine, cause the machine to perform the operations described in the following. The machine accessible medium may also include program code embedded therein. The program code may include machine readable code to perform the operations described in the following. The term "data" here refers to any type of information that is encoded for machine-readable purposes. Therefore, it may include program, code, data, file, etc.

[0022] All or part of an embodiment of the invention may be implemented by hardware, software, or firmware, or any combination thereof. The hardware, software, or firmware element may have several modules coupled to one another. A hardware module is coupled to another module by mechanical, electrical, optical, electromagnetic or any physical connections. A software module is coupled to another module by a function, procedure, method, subprogram, or subroutine call, a jump, a link, a parameter, variable, and argument passing, a function return, etc. A software module is coupled to another module to receive variables, parameters, arguments, pointers, etc. and/or to generate or pass results, updated variables, pointers, etc. A firmware module is coupled to another module by any combination of hardware and software coupling

PCT/CROODE / Out 3 8 0

methods above. A hardware, software, or firmware module may be coupled to any one of another hardware, software, or firmware module. A module may also be a software driver or interface to interact with the operating system running on the platform. A module may also be a hardware driver to configure, set up, initialize, send and receive data to and from a hardware device. An apparatus may include any combination of hardware, software, and firmware modules.

[0023] One embodiment of the invention may be described as a process, which is usually depicted as a flowchart, a flow diagram, a structure diagram, or a block diagram. Although a flowchart may describe the operations as a sequential process, many of the operations can be performed in parallel or concurrently. A loop or iterations in a flowchart may be described by a single iteration. It is understood that a loop index or loop indices or counter or counters are maintained to update the associated counters or pointers. In addition, the order of the operations may be re-arranged. A process terminates when its operations are completed. A process may correspond to a method, a program, a procedure, etc. A block diagram may contain blocks or modules that describe an element, an item, a component, a device, a unit, a subunit, a structure, a method, a process, a function, an operation, a functionality, or a task, etc. A functionality or an operation may be performed automatically or manually.

[0024] Figure 1A is a diagram illustrating a system 10 in which one embodiment of the invention can be practiced. The system 10 includes an ingress processor 20, an egress processor 30, a physical layer device 40, a fabric interface device 50, an interconnect interface 60, and a host processor system 70. Note that the system 10 may include more or less than the above elements. The system 10 represents an Ethernet processing unit for a number of network protocols or standards such as Synchronous Optical Network (SONET), Synchronous Digital Hierarchy (SDH), Asynchronous Transfer Mode (ATM), etc.

[0025] The ingress processor 20 may perform a number of network tasks such as segmentation and re-assembly (SAR), classification, metering, policing, initial congestion management, etc. The egress processor 30 may perform functions such as traffic shaping, etc. The ingress and egress processors 20 and 30 may be the same or different. They may be network processors, digital signal processors, controllers, or





any processors that may perform network functions. In one embodiment, the ingress and egress processors 20 and 30 are multi-threaded network processors. They may support a wide variety of wide are network (WAN) and local area network (LAN) with speeds ranging from Optical Carrier Level 3 (OC-3) to OC-192, or 155.52 Megabits per second (Mbps) to 10 Gigabits per second (Gbps). Each of the ingress and egress processors 20 and 30 may have a number of integrated micro-engines. Each microengine may be configured to have multiple threads (e.g., 4 or 8). In addition, they may include integrated core processor, cryptographic units, dynamic random access memory (DRAM) interfaces, static random access memory (SRAM) interfaces, media switch fabric interface, interconnect interface, etc. The ingress processor 20 may have interfaces to an SRAM bank 22 and a DRAM bank 24. The SRAM bank 22 may include a number of quad data rate (QDR) SRAM devices to store fast access network data such as queues and tables. The DRAM bank 24 may include a number of high performance DRAM devices to store packet data, program, or other data. Similarly, the egress processor 30 may have interfaces to an SRAM bank 32 and a DRAM bank 34 with similar functionalities. The egress processor 30 may provide flow control to the ingress processor 20.

[0026] The physical layer device 40 may provide interface to physical layer data. It may support various modes of operation for transport of Synchronous Transport Signal (STS)-192c/ Synchronous Transport Module (STM) 64c and 10 Gigabit Ethernet, high level data link control (HDLC) frame, Packet over SONET (POS), or generic framing procedure (GFP) packet formatting. It may include internal mapping engines to provide the required formatting and maintenance of packet data into the STS-192c/STM 64c SONET/SDH frame payload. It may include 10 Gigabit media access controller (MAC) to perform frame encapsulation, verification, flow control, statistics management.

[0027] The fabric interface device 50 may provide interface to a switch fabric that may be connected to a network. The interconnect interface 60 may provide interface to interconnect such as peripheral component interconnect (PCI). The host processor system 70 may provide control function or program development. It may be used to develop code to be downloaded or transferred to the program memory of the ingress or egress processors 20 and 30.



[0028] Figure 1B is a diagram illustrating a host processor system 70 according to one embodiment of the invention. The system 70 includes a processor unit 110, a memory controller (MC) 120, a main memory 130, an input/output controller (IOC) 140, an interconnect 145, a mass storage interface 150, and input/output (I/O) devices 160₁ to 160_k.

[0029] The processor unit 110 represents a central processing unit of any type of architecture, such as processors using hyper threading, security, network, digital media technologies, single-core processors, multi-core processors, embedded processors, mobile processors, micro-controllers, digital signal processors, superscalar computers, vector processors, single instruction multiple data (SIMD) computers, complex instruction set computers (CISC), reduced instruction set computers (RISC), very long instruction word (VLIW), or hybrid architecture

[0030] The MC 120 may provide control and configuration of memory and input/output devices such as the main memory 130 and the IOC 140. The MC 120 may be integrated into a chipset that integrates multiple functionalities such as graphics, media, isolated execution mode, host-to-peripheral bus interface, memory control, power management, etc. The MC 120 or the memory controller functionality in the MC 120 may be integrated in the processor unit 110. In some embodiments, the memory controller, either internal or external to the processor unit 110, may work for all cores or processors in the processor unit 110. In other embodiments, it may include different portions that may work separately for different cores or processors in the processor unit 110.

[0031] The main memory 130 stores system code and data. The main memory 130 is typically implemented with dynamic random access memory (DRAM), static random access memory (SRAM), or any other types of memories including those that do not need to be refreshed. The main memory 30 may include multiple channels of memory devices such as DRAMs. It may include a compiler or program translator or program transformer 135 to compile, translate, or transform the program code to be used by the egress or ingress processor 20 or 30 shown in Figure 1A. In particular, it includes a compiler to perform latency hiding using a coloring approach.

[0032] The IOC 140 may have a number of functionalities that are designed to support I/O functions. The IOC 140 may also be integrated into a chipset together or separate from the MC 120 to perform I/O functions. The IOC 140 may include a number of interface and I/O functions such as peripheral component interconnect (PCI) bus interface, processor interface, interrupt controller, direct memory access (DMA) controller, power management logic, timer, system management bus (SMBus), universal serial bus (USB) interface, mass storage interface, low pin count (LPC) interface, etc.

[0033] The interconnect 145 may provide interface to peripheral devices. The interconnect 145 may be point-to-point or connected to multiple devices. For clarity, not all the interconnects are shown. It is contemplated that the interconnect 145 may include any interconnect or bus such as Peripheral Component Interconnect (PCI), PCI Express, Universal Serial Bus (USB), and Direct Media Interface (DMI), etc. In particular, the interconnect 145 interfaces to the interconnect interface 60 (Figure 1A) to allow the processor unit 110 to communicate with the ingress or egress processor 20 or 30.

[0034] The mass storage interface 150 may provide interface to mass storage devices that store archive information such as code, programs, files, data, and applications. The mass storage device may include compact disk (CD) read-only memory (ROM) 152, digital video/versatile disc (DVD) 154, floppy drive 156, and hard drive 158, and any other magnetic or optic storage devices. The mass storage device provides a mechanism to read machine-accessible media.

[0035] The I/O devices 160₁ to 160_K may include any I/O devices to perform I/O functions. Examples of I/O devices 160₁ to 160_K include controller for input devices (e.g., keyboard, mouse, trackball, pointing device), media card (e.g., audio, video, graphic), network card, and any other peripheral controllers.

[0036] One embodiment of the invention involves program traces that have accesses to a critical section (CS). Critical section is a common synchronization problem. There are a number of solutions to a critical section problem. One popular solution is the use of semaphore. Semaphore may be implemented by using a wait instruction before entering a CS and a signal instruction after leaving a CS.

PCT/(N2005 / 00 1 9 8 0

[0037] Figure 2A is a diagram illustrating a program module 200 of program traces with a critical section according to one embodiment of the invention. The program module 200 provides an example of multiple program traces having a critical section (CS) 1. The program module 200 includes blocks 1, 2, 3, 4, 5, 6, 7, 8, 9, and 10 referenced by the numeral labels 210, 220, 230, 240, 250, 252, 254, 260, 262, and 264, respectively.

[0038] Trace 1 includes blocks 1 210, block 4 240, block 5 250, and block 8 260. Trace 2 includes block 3 230, block 4 240, block 7 254, and block 10 264. The critical section 1 (CS1) includes blocks 1 through 10 but only block 4 240, block 5 250, block 6 252, and block 7 254 are colored. The CS1 begins at block 1 210, block 2 220, and block 3 230. The CS1 ends at block 8 260, block 9 262, and block 10 264.

[0039] In block 1 210, there is a memory access mem1 and a wait instruction "wait s1". The order of the instructions is "CS1 begin", "memory access 1", and "wait s1". The memory access "mem1" is in the same critical section as the "wait s1" instruction, i.e., "wait s1" is associated with the memory access "mem1". In block 3 230, there is a memory access "mem2" and a wait instruction "wait s2". The order of the instructions is "memory access 2", "CS1 begin", and "wait s2". The memory access "mem2" is associated with the wait instruction "wait s2" but is not in the same critical section with wait s2. Therefore, "wait s2" is not colored.

[0040] In this example, since the wait instruction "wait s1" is in the same critical section with the memory access "mem1", the latency of the memory access "mem1" cannot be overlapped with the latency and/or the computations of other threads. Therefore, latency hiding using multiple threads or multiple processes is not possible. To provide latency hiding, it is necessary to move, or to sink, the wait instruction "wait s1" out of the critical section whose associated memory access is "mem1". This is done for all wait instructions in all program traces that are in the same critical sections with the associated memory accesses.

[0041] One embodiment of the invention sinks the wait instructions globally and speculatively based on the program traces using a coloring approach. This may be accomplished by two stages. In the first stage, the compiler colors, or assigns unique codes to, the basic blocks and the wait instructions based on the program traces and the



critical sections. In the second stage, the compiler sinks the wait instructions down globally, i.e., across basic blocks, and speculatively, such that the wait instructions are in those traces are moved out of the associated critical sections.

[0042] Figure 2B is a diagram illustrating coloring blocks in the program traces according to one embodiment of the invention. Figure 2B illustrates the first stage applied to the program module 200 shown in Figure 2A.

[0043] Block 1 210, block 4, 240, and block 5 250 in trace 1 are colored to become block 1 215, block 4 242, and block 5 255, respectively. Each of these blocks is colored with the same color, or is assigned with the same code. Block 8 260 in trace 1 is not colored because it is the last block of the critical section 1. Block 3 230, block 4 240, and block 7 254 in trace 2 are colored to become block 3 235, block 4 245, and block 7 256, respectively. Each of these blocks is colored with the same color, or is assigned with the same code. The color of the blocks in trace 2 is different than the color of the blocks in trace 1. Note that block 4 has two colors corresponding to blocks 4 242 and 245 because it belongs to two different traces. Block 10 264 in trace 2 and block 9, 262 are not colored because they are the last blocks in CS1.

[0044] The wait instruction "wait s1" in the block 1 215 is also colored with the same color as the block 1 215 because it is in the same critical section CS1 with the associated memory access "mem1". The wait instruction "wait s2" in the block 3 235 is empty because it is not in the same critical section with the associated memory access "mem2".

[0045] The association of the blocks in the program traces with the color information may be carried out by a coloring technique described by the following pseudo-code. The pseudo-code uses a C-like language.

```
Input: the program flow graph and the selected traces

Output: BlockColorSet: basic block b 	o the set of colors for the blocks

WaitColorSet: wait instruction w 	o the set of colors for the wait instructions

MemoryAccess2Waits: memory access -> associated wait instructions ncolors = 0; inCrticalSection = inCrticalSectionNow = false; for (each trace t, where t is a sequence of basic blocks b_1 	o b_2 	o ... 	o b_n)
```



```
for (j from n to 1, where basic block b_i is a sequence of instructions i_1 \rightarrow i_2 \rightarrow ... \rightarrow i_m)
     inCrticalSection = inCrticalSectionNow;
     if (inCrticalSection == true)
        BlockColorSet[b_i] += ncolors;
     for (k from m to 1)
        if (instruction i_k is critical section begin)
           inCrticalSection = inCrticalSectionNow = false;
           WaitSet = \{\}
        else if (i_k is critical section end)
           inCrticalSectionNow = true;
           ncolors ++;
        else if (inCrticalSection == true)
           if (i_k is a wait instruction)
              WaitSet += i_k;
           else if (i_k) is a memory access and its associated wait instruction w is in
              WaitSet)
              WaitColorSet[w] += ncolors;
             MemoryAccess2Waits[i_k] += w;
  }
}
```

[0046] Blocks are colored when they are in the critical sections and on traces. The color of a block or blocks is not related to the color of the wait instruction. In the above pseudocode, the colors of the blocks are saved in the BlockColorSet[] array. The colors of the wait instructions are saved in the WaitColorSet[] array. The color of a wait instruction depends on the two conditions: (1) the wait instruction is in a critical section and on a trace or traces, and (2) any of its associated memory accesses are in the same critical section and on the same trace or traces.

[0047] After the blocks and the wait instructions are colored, the wait instructions are moved out of the corresponding critical sections. This may take place along the sequence of the blocks of each of the program traces. The sinking of the wait instructions may be carried out by a pseudo-code as follows. In the following pseudo-


code, an instruction is ready when it may be sunk down without any dependence constraint. An instruction is not ready when it may not be sunk down due to dependence constraints.

```
Input: the program flow graph
      the basic block b with multiple predecessors
      the coloring information
Output: the program flow graph after speculative code motion
for (each predecessor p of basic block b)
  if (BlockColorSet[p] is not empty)
     for (each instruction i that is in block p and is not in SinkSet)
       if (i is an instruction of wait s, i is ready in p,
          and either i does not exit or is not ready in some of the predecessors of b)
           if (the intersection of BlockColorSet[p] and WaitColorSet[i] is not
              empty)
           SinkSet += i:
          for (each predecessor q of b where i does not exit or is not ready)
             insert an instruction of send signal s into the end of q;
       }
     }
  }
}
```

Insert the instructions in SinkSet into the beginning of b;

[0048] Note that in the above pseudo-code, the BlockColorSet[p] contains the block color of the block p and the WaitColorSet[i] contains the wait color of the wait instruction i. If the intersection of these two sets is not empty, it means that the wait instruction i has the same color as the block p, and therefore it may be speculatively sunk down.

[0049] Figure 3A is a diagram illustrating speculative moving of wait instruction according to one embodiment of the invention. Figure 3A shows a transformation from Figure 2A. Block 1 215, block 2 220, block 3 235, blocks 4 242 and 245 in Figure 2A now become block 1 310, block 2 320, block 3 330, blocks 4 342 and 345, respectively.



[0050] The wait instruction "wait s1" is moved from block 1 310 to block 4 342. Since this wait instruction "wait s1" is eventually moved out of the critical section CS1, compensation code is inserted in block 2 320 and block 3 330 because the blocks are the predecessor blocks of blocks 4 342 and 345. In one embodiment, the compensation code is the "send signal s1" instruction.

[0051] Figure 3B is a diagram illustrating intermediate moving of wait instruction according to one embodiment of the invention. Block 5 255, block 6 252, and block 7 256 in Figure 2A become block 5 355, block 6 352 and block 7 356, respectively. Blocks 4 342 and 345 in Figure 3A become blocks 2 242 and 245.

[0052] The wait instruction "wait s1" is moved from block 4 242 to block 5 355, block 6 352, and block 7 356 because blocks 4 242 and 245 are the predecessor blocks of block 5 355, block 8 352, and block 7 356.

[0053] Figure 3C is a diagram illustrating final moving of wait instruction according to one embodiment of the invention. Block 5 355 and block 8 260 in Figure 3B become block 5 255 and block 8 360, respectively.

[0054] The wait instruction "wait s1" is moved from block 5 255 to block 8 360 because the color set of "wait s1" intersects with the color set of block 5. This means there should be any associated memory access instructions of "wait s1" are in the same critical section and on the same trace with "wait s1". "Memory access 1" is one of this kind of instruction in this example. The wait instructions "wait s1" in block 6 352 and block 7 356 remain there because these blocks do not belong to the trace 1.

[0055] After all the wait instructions or the beginnings of the critical sections sink across the basic blocks, the color information is updated to maintain the correctness of the program logic. The updating of the color information may be carried out by a pseudo-code as follows.

Input: the coloring information and the code motion information Output: the updated coloring information

for (each of the instructions of critical section begin that sinks out of basic block b)

{
 colorset = {c | color c is associated with the particular critical section};
 BlockColorSet[b] -= colorset;
 for (each memory access i in b)

```
for (each wait instruction w in MemoryAccess2Waits[i])
WaitColorSet[w] -= colorset;
}
}
```

for (each wait instruction w that sinks into basic block b)

WaitColorSet[w] = the intersection of WaitColorSet[w] and BlockColorSet[b];

[0056] Figure 4 is a diagram illustrating update of color information when sinking critical section begin according to one embodiment of the invention. The block 1 215, block 2 220, block 3 235, and blocks 4 242 and 245 in Figure 2A become block 1 410, block 2 420, block 3 430, and blocks 4 442 and 445, respectively.

[0057] The instructions CS1 begin in blocks 1, 2, and 3 are moved to block 4. The colors of blocks 1 410, 3 430, and the instruction "wait s1" in block 1 410 are all set to empty or reset.

[0058] Figure 5 is a flowchart illustrating a process 500 to hide latency of a program trace according to one embodiment of the invention. Each of the blocks in the process 500 may correspond to a module which may be a program module, a hardware circuit, a firmware module, or a combination of them. The process 500 may correspond to the program transformer 135 shown in Figure 1B.

[0059] Upon START, the process 500 associates blocks of instructions between the start and the end of a critical section with color information (Block 510). The blocks correspond to a program trace and contain a wait instruction. Then, the process 500 sinks the wait instruction down the blocks globally to the end of the critical section using the color information and a dependence constraint on the wait instruction (Block 520). A dependence constraint may be a constraint that limits the mobility of an instruction due to a dependency or a relationship between that instruction with another instruction. For example, there is a dependence constraint between a memory access instruction and a wait instruction associated with the memory access. The process 500 is then terminated.

[0060] Figure 6 is a flowchart illustrating a process 510 to associate blocks with color information according to one embodiment of the invention. The process 510 may correspond to the example shown in Figure 2B.

[0061] Upon START, the process 510 identifies a sequence of the blocks corresponding to the program trace from a starting block at the start of the critical section to an ending block at the end of the critical section (Block 610). The starting block contains the wait instruction. Then, the process 510 assigns a block color to the sequence of the blocks and a wait color to the wait instruction (Block 620). The block color or the wait color may be any uniquely identified code. In one embodiment, the block color or the wait color is a code that is incremented after an assignment. The process 510 is then terminated.

[0062] Figure 7 is a flowchart illustrating a process 520 to sink the wait instruction according to one embodiment of the invention. The process 520 may correspond to the example shown in Figure 3A.

[0063] Upon START, the process 520 speculatively moves the wait instruction to a basic block having multiple predecessor blocks (Block 710). The multiple predecessor blocks include the starting block. Then, the process 520 inserts compensation code to at least one of the multiple predecessors blocks excluding the starting block (Block 720). This is because the starting block belongs to the current trace, and the other predecessor blocks do not belong to the current trace. Next, the process 520 updates the color information (Block 730) and is then terminated.

[0064] Figure 8 is a flowchart illustrating a process 730 to update the color information according to one embodiment of the invention. The process 730 may correspond to the example shown in Figure 4.

[0065] Upon START, the process 730 resets the block color of the basic block (Bock 810). In one embodiment, resetting may be performed by decrementing the color code. Next, the process 730 resets the wait color of the wait instruction having an associated memory access instruction in the basic block (Block 820). Then, the process 730 changes the color of the wait instruction to intersection of reset color of the wait instruction and the reset color of the basic block (Block 830). Then, the process 730 is terminated.

[0066] Figure 9 is a diagram illustrating a program transformer 135 to enhance latency hiding according to one embodiment of the invention. The program transformer 135

may be implemented by software, hardware, firmware, or any combination of these elements. It includes a color associator 920 and a code mover and compensator 930. Note that the compiler 135 may include more or less than the above elements.

[0067] The color associator 920 associates blocks of instructions between start and end of a critical section with color information. The blocks correspond to a program trace and containing a wait instruction. The color associator 920 includes a trace identifier 922 and a color assigner 924. The trace identifier 922 identifies the program traces in a program module 910. It may collect blocks belonging to each program trace. It identifies critical sections, start and end of the critical sections, the memory access instructions, and all the relevant wait instructions. The relevant wait instructions are those instructions that are in the same critical section that contain the associated memory access instructions. The color assigner 924 colors, or assigns codes to, the blocks and the corresponding wait instruction for all the program traces identified by the trace identifier or collector 922.

[0068] The code mover and compensator 930 includes a code mover 932, a code compensator 934, and a color updater 936. The code mover 922 sinks the wait instruction down the blocks globally to the end of the critical section using the color information and a dependence constraint on the wait instruction. The code mover 922 moves the wait instruction to the basic block if the block color of the starting block and the wait color of the wait instruction have same color and if the wait instruction is ready. The code compensator 934 inserts a compensation code to predecessor blocks of a basic block. In one embodiment, it inserts a send signal to the at least one of the multiple predecessors excluding the starting block. The color updater 936 updates the color information to maintain program correctness. It resets block the color of the basic block, and the wait color of the wait instruction having an associated memory access instruction in the basic block. It may also change the wait color of the wait instruction to intersection of reset wait color of the wait instruction and the reset block color of the basic block.

[0069] The output of the code mover and compensator 930 is an enhanced program module 960. The enhanced program module 940 now has all wait instructions moved

PCT/CN 2005 / 0 0 1 9 6 0

out of corresponding critical sections. Therefore, it may be processed by a multi-

thread/multi-process module that hides memory access latencies.

[0070] While the invention has been described in terms of several embodiments, those of ordinary skill in the art will recognize that the invention is not limited to the embodiments described, but can be practiced with modification and alteration within the spirit and scope of the appended claims. The description is thus to be regarded as illustrative instead of limiting.

PCI/CN 2005 / 0 0 1 9 6 0

CLAIMS

What is claimed is:

1. A method comprising:

associating blocks of instructions between start and end of a critical section with color information, the blocks corresponding to a program trace and containing a wait instruction; and

sinking the wait instruction down the blocks globally to the end of the critical section using the color information and a dependence constraint on the wait instruction.

- 2. The method of claim 1 wherein associating the blocks comprises: identifying a sequence of the blocks corresponding to the program trace from a starting block at the start of the critical section to an ending block at the end of the critical section, the starting block containing the wait instruction; and assigning a color to the sequence of the blocks and the wait instruction.
- 3. The method of claim 1 wherein sinking the wait instruction comprises: speculatively moving the wait instruction to a basic block having multiple predecessor blocks, the multiple predecessor blocks including the starting block; inserting compensation code to at least one of the multiple predecessors excluding the starting block; and updating the color information.
- 4. The method of claim 3 wherein speculatively moving the wait instruction comprises:

moving the wait instruction to the basic block if the starting block and the wait instruction have same color and if the wait instruction is ready.

5. The method of claim 3 wherein inserting the compensation code comprises:

inserting a send signal to the at least one of the multiple predecessors excluding the starting block.

6. The method of claim 3 wherein updating the coloring information comprises:

resetting the color of the basic block; and
resetting the color of the wait instruction having an associated memory access
instruction in the basic block.

7. The method of claim 6 wherein updating the color information further comprises:

changing the color of the wait instruction to intersection of reset color of the wait instruction and the reset color of the basic block.

8. A program transformer comprising:

a color associator to associate blocks of instructions between start and end of a critical section with color information, the blocks corresponding to a program trace and containing a wait instruction; and

a code mover and compensator coupled to the color associator to sink the wait instruction down the blocks globally to the end of the critical section using the color information and a dependence constraint on the wait instruction.

9. The program transformer of claim 8 wherein the color associator comprises:

a trace identifier to identify a sequence of the blocks corresponding to the program trace from a starting block at the start of the critical section to an ending block at the end of the critical section, the starting block containing the wait instruction, and

a color assigner coupled to the trace identifier to assign a block color to the sequence of the blocks and a wait color to the wait instruction.

10. The program transformer of claim 8 wherein the code mover and compensator comprises:

a code mover to speculatively move the wait instruction to a basic block having multiple predecessor blocks, the multiple predecessor blocks including the starting block;

a code compensator to insert compensation code to at least one of the multiple predecessors excluding the starting block; and

a color updater to update the color information.

- 11. The program transformer of claim 10 wherein the code mover moves the wait instruction to the basic block if the block color of the starting block and the wait color of the wait instruction have same color and if the wait instruction is ready.
- 12. The program transformer of claim 10 wherein the code compensator inserts a send signal to the at least one of the multiple predecessors excluding the starting block.
- 13. The program transformer of claim 10 wherein the color updater resets the block color of the basic block, and the wait color of the wait instruction having an associated memory access instruction in the basic block.
- 14. The program transformer of claim 10 wherein the color updater changes the wait color of the wait instruction to intersection of reset wait color of the wait instruction and the reset block color of the basic block.
 - 15. A system comprising:
 - a network processor;
 - a host processor coupled to the network processor; and
- a memory coupled to the host processor having a program transformer to transform a program module to be executed on the network processor, the program transformer comprising:
 - a color associator to associate blocks of instructions between start and end of a critical section with color information, the blocks corresponding to a program trace and containing a wait instruction, and a code mover and compensator coupled to the color associator to sink the wait instruction down the blocks globally to the end of the critical section using the color information and a dependence constraint on the wait instruction.
- 16. The system of claim 15 wherein the color associator comprises:
 a trace identifier to identify a sequence of the blocks corresponding to the
 program trace from a starting block at the start of the critical section to an ending block
 at the end of the critical section, the starting block containing the wait instruction; and

PCI/CN 2005 / 0 0 1 9 6 6

a color assigner coupled to the trace identifier to assign a block color to the sequence of the blocks and a wait color to the wait instruction.

17. The system of claim 15 wherein the code mover and compensator comprises:

a code mover to speculatively move the wait instruction to a basic block having multiple predecessor blocks, the multiple predecessor blocks including the starting block:

a code compensator to insert compensation code to at least one of the multiple predecessors excluding the starting block; and

a color updater to update the color information.

- 18. The system of claim 17 wherein the code mover moves the wait instruction to the basic block if the block color of the starting block and the wait color of the wait instruction have same color and if the wait instruction is ready.
- 19. The system of claim 17 wherein the code compensator inserts a send signal to the at least one of the multiple predecessors excluding the starting block.
- 20. The system of claim 17 wherein the color updater resets the block color of the basic block, and the wait color of the wait instruction having an associated memory access instruction in the basic block.
- 21. The system of claim 17 wherein the color updater changes the wait color of the wait instruction to intersection of reset wait color of the wait instruction and the reset block color of the basic block.
 - 22. An article of manufacture comprising:

a machine-accessible medium including data that, when accessed by a machine, cause the machine to perform operations comprising:

associating blocks of instructions between start and end of a critical section with color information, the blocks corresponding to a program trace and containing a wait instruction; and

sinking the wait instruction down the blocks globally to the end of the critical section using the color information and a dependence constraint on the wait instruction.

23. The article of manufacture of claim 22 wherein the data causing the machine to perform associating the blocks comprises data that, when accessed by a machine, cause the machine to perform operations comprising:

identifying a sequence of the blocks corresponding to the program trace from a starting block at the start of the critical section to an ending block at the end of the critical section, the starting block containing the wait instruction; and

assigning a block color to the sequence of the blocks and a wait color to the wait instruction.

24. The article of manufacture of claim 22 wherein the data causing the machine to perform sinking the wait instruction comprises data that, when accessed by a machine, cause the machine to perform operations comprising:

speculatively moving the wait instruction to a basic block having multiple predecessor blocks, the multiple predecessor blocks including the starting block;

inserting compensation code to at least one of the multiple predecessors excluding the starting block; and

updating the color information.

25. The article of manufacture of claim 24 wherein the data causing the machine to perform speculatively moving the wait instruction comprises data that, when accessed by a machine, cause the machine to perform operations comprising:

moving the wait instruction to the basic block if the block color of the starting block and the wait color of the wait instruction have same color and if the wait instruction is ready.

26. The article of manufacture of claim 24 wherein the data causing the machine to perform inserting the compensation code comprises data that, when accessed by a machine, cause the machine to perform operations comprising:

inserting a send signal to the at least one of the multiple predecessors excluding the starting block.

110/14/14/14/1/101980

27. The article of manufacture of claim 24 wherein the data causing the machine to perform updating the coloring information comprises data that, when accessed by a machine, cause the machine to perform operations comprising:

resetting the block color of the basic block; and

resetting the wait color of the wait instruction having an associated memory access instruction in the basic block.


28. The article of manufacture of claim 27 wherein the data causing the machine to perform updating the color information further comprises data that, when accessed by a machine, cause the machine to perform operations comprising:


changing the wait color of the wait instruction to intersection of reset block color of the wait instruction and the reset block color of the basic block.

PCT/CN 2005 / 0 0 1 9 6 0

ABSTRACT OF THE DISCLOSURE

An embodiment of the present invention is a technique to hide latency in program traces. Blocks of instructions between start and end of a critical section are associated with color information. The blocks correspond to a program trace and containing a wait instruction. The wait instruction is sunk down the blocks globally to the end of the critical section using the color information and a dependence constraint on the wait instruction.







3/11




FIG. 2A







FIG. 2B















FIG. 4










FIG. 9